

May 2, 2019

Posted via PDF (2 pages)

**ADDENDUM No. 2
REQUEST FOR TENDER No. 143-2019
CONTRACT No. 19ECS-TI-09MR
CLOSING DATE: 12:00 NOON (LOCAL TIME), May 6, 2019**

For: Reconstruction of Willowdale Avenue from Finch Avenue to Empress Avenue

Please refer to the above Request for Tender (RFT) document in your possession and be advised of the following:

I. QUESTIONS & ANSWERS

Q1. Can you please clarify the types of utilities to be adjusted in item #29 of the tender named in the subject line?

A1. Please see clause 24 (Utility Adjustment - RD422SS) in section 4a of the tender document and Toronto Specification TS4.50.

Q2. Can you please clarify where sod restoration will be paid for, when adjacent to sidewalks and curbs? Is this to be bid under the respective concrete sidewalk or concrete curb item? Or will it be paid for under the nursery sod item?

A2. Unless addressed in the Specifications under "Measurement For Payment" or "Basis of Payment" all restorations will be paid under the appropriate tender items for the restoration. (ie. Sod, driveways, etc).

Q3. If tree protection or a Tree protection plans is considered incidental to the work, which items are the contractor to use so that our bid is not deemed unbalanced by the city. Can the city add an item for tree protection?

A3. The cost of producing and implementing a tree protection plan and any associated costs should be split among all items that may impact existing trees. Please review Section 4a, Supplemental Specification #13, Tree Protection – GN128SS of the tender document. If the identified guidelines are adhered to, the cost of tree protection should not be significant.

Q4: With respect to the asbestos impacted asphalt removal, is the assumption to be that there are certain areas where there is only one lift of asphalt that has asbestos in it? Or wherever there is asbestos in the asphalt, it is to be assumed that the full pavement

markup is affected by asbestos? Asbestos removal plan shows that there are some areas where only the middle layer (40mm to 90mm) is affected by asbestos. Please clarify.

A4. Asbestos was observed to be either in the top layer, middle layer or top and middle layer of asphalt. Only the layers within the areas where asbestos was observed, will the asbestos be removed and disposed of accordingly.

Q5. The diagram that shows the asbestos removal plan, shows that there are (1) areas where asbestos impacted asphalt is only in the top 40mm, (2) other areas where it is in between 40mm and 90mm deep, and (3) other areas where it is up to 90mm deep. Please clarify the difference between area 3 and areas 1 & 2, as area 3 would also be included in areas 1 and 2.

A5. Please review the staging plan in section 4 of the tender package, along with the asbestos removal plan and the answer above.

In summary:

1) Areas of pavement where asbestos was observed in the top layer only, a 40mm grind will be required under item 19 of the pricing form; followed by full depth removal of the remaining flexible pavement under item 23 of the pricing form.

2) Areas of pavement where asbestos was observed in both the top layer and middle layer, a 90mm grind will be required under item 20 of the pricing form; followed by full depth removal of the remaining flexible pavement under item 23 of the pricing form.

3) areas of pavement where asbestos was observed in the middle layer only (40mm to 90mm), a regular (non-asbestos containing) 40mm grind will be required under item 21 of the pricing form, followed by a 50mm grind of the asphalt where asbestos was observed (middle layer) under item 19 of the pricing form; followed by full depth removal of the remaining flexible pavement under item 23 of the pricing form.

4) Areas of pavement where no asbestos was observed, full depth removal of the flexible pavement will be required under item 23 of the pricing form.

Should you have any questions regarding this addendum contact Christina Kysym by email at Christina.Kysym@toronto.ca.

Please attach this addendum to your RFT document and be governed accordingly. Tenderers are to acknowledge receipt of all addenda in their Tender in the space provided on the Tender Cover Page as per Section 1 – Tender Process Terms and Conditions, item 10 of the RFT document. All other aspects of the RFT remain the same.

Thank you,

Sabrina Dipietro
Acting Manager, Construction Services
Purchasing and Materials Management Division